



**THE CITY OF MARIETTA  
MARIETTA, GEORGIA**

July 9, 2015

**ADDENDUM NO. 1  
TO  
CITY OF MARIETTA BID NO. RFB-15-37674  
FOR  
2015 SUMMER REPAVING PROJECT**

**Change or add the following in the above referenced bid:**

**The following questions were asked.**

1. On page 1.1 of the Project Manual it states that the work for the project shall be performed Monday thru Saturday 7:00am to 7:00pm however later on in the documents in the General Conditions there are work restrictions that conflict with these work hours. Please provide a clarification on which is the correct work hours. This will have a profound impact on the production and cost of the work.

**Monday-Saturday 7am-7pm**

2. It appears that the only street that will be "Edge Milled" is Allgood Road and that all other roads will receive full width milling, can you please confirm that this is correct? If not can you identify which streets get full width milling and which get edge milling?

**Allgood Road is the only street edge milled for bidding purposes.**

3. Can you confirm that the Water Valve and Manhole Adjustments will be performed after the completion of the Milling, Patching and 12.5mm placement?

**Yes, adjust to grades after paving.**

4. Can you please confirm that the GDOT Asphalt Cement Index will not apply to this project?

**Confirmed**

5. Will the Contractor be allowed to use Portable Advanced Warning sign for this project?

**All traffic control will be per MUTCD and the responsibility of the contractor. Portable Advanced warning signs are allowed.**

6. If required will the City provide Marietta Police to direct traffic on Streets that have work that will interfere or extend into intersections that have traffic signals?

All traffic control will be per MUTCD and the responsibility of the contractor. It should be included in the bid.

7. Will the Contractor be required to install Low/Soft Shoulder signs on any of the streets or are all streets curbed?

All traffic control will be per MUTCD and the responsibility of the contractor.

8. Will the City require the Contract to use a Shuttle Buggy (aka Material Transfer Vehicle) for the placement of the 12.5mm mix?

This is not required on the project.

9. I don't recall seeing a construction detail for the Speed Table bid item, could you please provide this information?

The speed table will be deleted from the contract. See attached revised bid schedule

10. Do you have the patching quantities for each of the streets, this is extremely helpful in determining the cost of the work.

Patching quantities for all streets except Allgood Rd were calculated using an estimate of 15% of milled area.

All other terms and conditions will remain the same.